



NOTES:

1. CONTRACTOR TO INSTALL/METER BOX AND ANGLE METER STOP. METER & BACKFLOW PREVENTION ASSEMBLY WILL BE SET BY CITY UPON REQUEST/PAYMENT.
2. METER BOXES SHALL NOT BE INSTALLED WITHIN SIDEWALK OR PAVED AREAS.
3. PROVIDE WATER METER BOX AS FOLLOWS OR EQUAL: COPY
 BOX BODY - POLYMER SHEET MOULD COMPOSITE 17x30x18" DEEP
 BOX LID - POLYMER CONCRETE MARKED WATER WITH TOUCH READ PAD.
4. METER BOX SET 4" MIN. BEHIND CURB OR SIDEWALK OR BEHIND CURB WHEN SIDEWALK IS PROPERTY TIGHT.
5. CITY STANDARD "MUELLER" BRASS FITTINGS OR EQUIVALENT.
6. WATER SERVICE TO BE: 1" IRON PIPE SIZE, CLASS 200, HDPE 3408, SIDR 7, BLUE, MEETING AWWA C901, AND ASTM D-2239
7. MAINTAIN 18-INCHES MINIMUM COVER OVER SERVICE LINE.

**CITY OF FLORENCE
STANDARD DRAWING**

**1" WATER
SERVICE**

DATE: MAY-2011	DRAWING NO. F-408B
-------------------	-----------------------